


#### **Wolftrap Creek Stream Restoration**



- > Project Overview
- > Background
- Objectives
- > Existing Conditions
- > Plan Review
- > Examples
- > Next Steps

Fairfax County Stormwater Management



### **Overview – Program Drivers**

#### The Clean Water Act of 1972 ...

"fishable and swimmable waters of the United States"

- Chesapeake Bay Agreement
- Executive Order
- > State and Federal Standards
  - Municipal Separate Storm Sewer Permit (MS-4)
    - > Easements rights and responsibility to maintain/upgrade
  - Forthcoming Requirements
    - Total Maximum Daily Loads (TMDL)
    - Regulates amounts of pollutants in waterways



#### **Project Objectives**

# Restore ~ 2500 LF from Follin Lane to downstream end of Wildwood Park

- Maximize ecological potential
- Stabilize streambed and banks
- Minimize loss of trees
- Maintain close coordination with stakeholders
  - Continuity of trail use



#### **Social Goals**

- Recreation
- Community enhancement
- Educational opportunities
- Community involvement
- Open lines of communication
- Integrate concerns and desires of the community into the project design
- Example for rest of community



#### **Project Objectives**


#### **Stream Restoration**

- More like "rehabilitation". Restoring multiple environmental values and as much environmental health and integrity as possible.
- Return structure, functions, and dynamics to the maximum extent possible given the constraints of our modern, developed landscape.

- Most Fairfax County streams are responding to anthropogenic alteration of the landscape.
- Eight variables which shape and maintain stream channels:
  - discharge
  - width
  - depth
  - velocity
  - slope
  - channel roughness
  - bedload size
  - bedload volume

#### Indicators of a degraded stream channel;

- Downed trees
- Channel incision and widening
- Channel Scour
- Sediment aggradations
- Poor instream habitat
- Low plant species diversity



Fairfax County Stormwater Management



EXISTING CONDITION - LOOKING UPSTREAM AT ERODING MEANDER.






EXISTING CONDITION - STREAM CHANNEL ENCROACHING ON EXISTING PAVED TRAIL.






EXISTING CONDITION - LOOKING UPSTREAM AT THE CONFLUENCE OF TRIBUTARY 1 AND WOLF TRAP CREEK.

















Fairfax County Stormwater Management




Fig. 8.46



Fig. 8.37b - A stabilized streambank, after establishment of remedial measures. In Stream Corridor Restoration: Principles, Processes, and Practices, 10/98. Interagency Stream Restoration Working Group (FISRWG)(15 Federal agencies of the US).

Rooted/leafed condition of the living plant material is not representative at the time of installation. Source: Chapter 16 Engineering Handbook, USDA-NRCS, 1997.

Fig. 8.40 — Cutting systems. Details of brushmattressing techniques. In Stream Corridor Restoration: Principles, Processes, and Practices, 10/98. Interagency Stream Restoration Working Group (FISRWG)(15 Federal agencies of the US).



#### In-stream Structures: Rock Cross Vane








#### In-stream Structures: Step Pools







#### **Structures: Riffle**
























#### Construction





CONTAINER PLANTING ZONE		SPECIES GROUP <sup>1,2</sup>		INDICATOR STATUS	PLANT SPACING <sup>3</sup>	CONTAINER SIZE, RATE, AND QUANTITY <sup>4</sup>	
						PLANTS PER ACRE	# OF PLANTS
RIPARIAN FOREST	TREE LAYER	À	QUERCUS ALBA (WHITE OAK)	FACU-	20100501	300 ONE-GALLON - or - 600 TUBELINGS - or - MIX AT 1:2 RATIO (SEE NOTE #4)	405 (BASED ON ONE-GALLON)
			QUERCUS BICOLOR (SWAMP WHITE OAK)	FACW+	SEE NOTE #3		
			QUERCUS PALUSTRIS (PIN OAK)	FACW			
			QUERCUS PHELLOS (WILLOW OAK)	FAC+			
			QUERCUS RUBRA (NORTHERN RED OAK)	FACU-			
		2	ACER NEGUNDO (BOX ELDER)	FAC+	SEE NOTE #3	150 ONE-GALLON —or— 300 TUBELINGS —or— MIX AT 1:2 RATIO (SEE NOTE #4)	204 (BASED ON ONE-GALLON)
			ACER RUBRUM (RED MAPLE)	FAC			
			BETULÁ NIGRA (RIVER BIRCH)	FACW			
			LIQUIDAMBAR STYRACIFULA (SWEET GUM)	FAC			
			NYSSA SYLVATICA (BLACK GUM)	FACW+			
			PLATANUS OCCIDENTALIS (AMERICAN SYCAMORE)	FACW-			
		3	LEX OPACA (AMERICAN HOLLY)	FACU+	SEE NOTE #3	100 ONE-GALLON or 200 TUBELINGS or MIX AT 1:2 RATIO (SEE NOTE #4)	135 (BASED ON ONE-GALLON)
	SHRUB LAYER	4	AMELANCHIER CANADENSIS (CANADIAN SERVICEBERRY)	FAC	SEE NOTE #3	150 ONE-GALLON -or- 300 TUBELINGS -or- MIX AT 1:2 RATIO (SEE NOTE #4)	204 (BASED ON ONE-GALLON)
			CERCIS CANADENSIS (EASTERN REDBUD)	FACU-			
			CORNUS FLORIDA (FLOWERING DOGWOOD)	FACU-			
			CORYLUS AMERICANA (AMERICAN HAZELNUT)	FACU-			
			LINDERA BENZON (NORTHERN SPICEBUSH)	FACW-			
			VIBURNUM DENTATUM (SOUTHERN ARROWWOOD)	FAC			
			VIBURNUM PRUNIFOLIUM (BLACK-HAW)	FACU			
RIPARIAN	FOREST (	QUANTIT	Y SUBTOTALS			700	948
STREAM BANK	TREE AND SHRUB LAYER	5	CORNUS AMOMUM (SILKY DOGWOOD)	FACW		· N/A	(BASED ON ONE-GALLON)
			LEX VERTICULATA (COMMON WINTERBERRY)	FACW+	SEE NOTE #3 (AVERAGES		
			SAMBUCUS CANADENSIS (ELDERBERRY)	FACW-	3' O.C. FOR ONE-GALLON)		
			VIBURNUM DENTATUM (SOUTHERN ARROWWOOD)	FAC			
	TREE LAYER	6	PLATANUS OCCIDENTALIS (AMERICAN SYCAMORE)	FACW-	SEE NOTE #3	N/A	540 (BASED ON ONE-GALLON)
			BETULA NIGRA (RIVER BIRCH)	FACW	(AVERAGES 6' O.C. FOR ONE-GALLON)		
TREAM	BANK QUA	NTITY S	UBTOTALS		ONE-GALLON)		1,620
			ALNUS SERRULATA (BROOKSIDE ALDER)	OBL			
		7	CORNUS AMOMUM (SLKY DOGWOOD)	FACW	1" O.C. SEE NOTES #5, #6)	N/A	3,242 (TUBELINGS OR LIVESTAKES
стрель	TREFAND	7					
STREAM EDGE	TREE AND SHRUB LAYER	7	SALIX NIGRA (BLACK WILLOW)	FACW+			UVESTAKES ONLY - SEE



### **Example: Poplar Springs Stream Restoration Burke, VA**

Before Afte












Fairfax County Stormwater Management











Fairfax County Stormwater Management







Competed Project: Bridle Path

#### Before Construction: Severe Streambank Erosion along Property Lines



Competed Project: Bridle Path

#### **Post Construction**





Competed Project: Bridle Path

#### **Post Construction**





#### **McLean Community Center**

Before
































#### **Next Steps**

#### **Project Schedule**

#### Phase I

- 100% Design Complete 6/2011
- Public Bid/Construction Contract 6/2011-8/2011
- Construction Start 9/2011 (After PHRA Season)
- Construction Completion 1/2012

#### Phase II

- To Be Determined
- Stakeholder participation and funding availability





#### **Contact Information**

Justin Pistore – Project Manager 703-324-5685 justin.pistore@fairfaxcounty.gov

**Fairfax County Stormwater Planning Division** 

703-324-5500 TTY 711
12000 Government Center Parkway
Suite 449
Fairfax, Virginia 22035
www.fairfaxcounty.gov/dpwes/stormwater

To request this information in an alternate format call 703-324-5500, TTY 711



